

Pre Terminated 1U Rackmount Patch Panel



Dimension(HxWxD): **483mmx280mmx44mm**

Fiber Termination Units are used for termination and management of Fiber backbone and equipment cables in Central Office and bulk fiber distribution systems. It serves as the interface between field cables and equipment. The 24-fiber cable stub is pre-terminated with SC connectors in the enclosure. Riser-rated and Indoor/Outdoor cable stubs are available in different lengths.

Fabricated from 1.2 to 1.6 mm thick carbon steel, these panels are pre treated and painted with enamel or powder coated to ensure corrosion resistance. Rack mounted versions are designed for flange mounting on 19 inch racks. Finished in standard colours.

Applications

- ❖ FTTH Deployments
- ❖ Optical CATV Networks
- ❖ Passive Optical Networks (PON)
- ❖ Telecom Networks

Product features

- ❖ Number of Ports upto 24F.
- ❖ Provision for cable anchoring; cable straps included
- ❖ Multiple connector options. Easy inter-changeability.
- ❖ Slack space for easy cable management.
- ❖ Cable entry from rear side. Radius controlled cable routing.
- ❖ Draw out or fixed termination tray options.
- ❖ Front Access to cable connectors.
- ❖ Screen printed panels for easy identification.

Specification

Insertion Loss : 0.30dB Max
 Back Refection : > 50dB (SC/PC)
 > 60dB (SC/APC)

Ordering Information

